



Town of South Windsor BONDED CAPITAL PROJECTS

NEVERS ROAD RECONSTRUCTION AND DRAINAGE

Project Description

Nevers Road has a long flat spot with very poor drainage from Miller Road south to just past Hayes Road. Puddles form on the side of the road and just off the road in resident's driveways and yards in this area after heavy rain storms. In winter these puddles freeze requiring repeated trips by Town crews to treat the road for snow/ice control. The Town has installed some drywells in this area to collect the water and reduce the puddles in private driveways but this has not solved all the problems. There is an old storm drain pipe along the side of Nevers Road but it is inadequate and all storm water does not drain to the few catch basins in this area.

Recommended Solution

New drainage pipes and catch basins will be installed along Nevers Road between Miller Road and Lake Street. About 1200 feet of Nevers Road in this area will be regraded to eliminate the flat areas and create high and low points to get the storm water to flow to the new drainage structures.

Schedule

Engineering	75% complete
Easements/ROW	Fall 2008
Construction	Spring, Summer 2009

Status (as of 7/7/08)

The design of the new drainage system is about 75% complete. More new drainage pipes and catch basins will be required than were originally proposed because of the poor condition of the existing system.

